

# Dialysis Access Institute

The Regional Medical Center - Orangeburg, SC

16,000 Sq Feet



New construction of a free standing, 16,000 SF fully integrated Dialysis Access Institute. The new facility has (6) PRE-OP stations and (6) POST-OP stations, (5) Operating/Procedure suites, Recovery Room and Patient rooms and offices. Mechanical design is comprised of chilled water RTU's ducted to VAV's with electric heat. Air distribution includes

(3) periflow operating room hood systems. Control system is DDC Trane controls. MEDGAS system includes outlet stations for (6) OR/Procedure rooms with Pattons Packaged Vacuum and Medical Gas Air Compressors. Our scope also included Plumbing system which consists of Gas Water Heaters and typical fixtures throughout.