

Palmetto Health Richland

Columbia, SC
Cooling Towers & Piping



Installation of three new cooling towers to serve the Hospital Campus. Work included demolition of existing cooling towers, piping and electrical power to the equipment. Work to set the new Cooling Towers was phased to minimize disruptions to the Hospital. Prep work included underground process piping, electrical requirements, and reinforced concrete footings. All associated piping, pumps, valves and controls completed. New condenser water system including a common return and supply heater that allows air handler unit chiller/cooling tower/pump combination to be utilized.